GENERAL NOTES


- BOUNDARY AND TOPOGRAPHIC INFORMATION HAVE BEEN TAKEN FROM SURVEY ENTITLED "EXISTING CONDITIONS MAP", PREPARED BY ARTHUR H. HOWLAND & ASSOCIATES, P.C., PREPARED FOR ARADEV LLC, DATED JULY 16, 2024, SCALED 1"=50'.
- 2. NORTH ARROW AND BEARINGS ARE BASED UPON THE CONNECTICUT GRID SYSTEM (CTGS).
- 3. ELEVATIONS, CONTOUR AND BENCHMARKS ARE BASED UPON NAVD 1988.
- 4. INFORMATION REGARDING THE LOCATION OF EXISTING UTILITIES HAS BEEN BASED UPON AVAILABLE INFORMATION AND MAY BE INCOMPLETE, AND WHERE SHOWN SHOULD BE CONSIDERED APPROXIMATE. THE LOCATION OF ALL EXISTING UTILITIES SHOULD BE CONFIRMED PRIOR TO BEGINNING CONSTRUCTION. CALL "CALL BEFORE YOU DIG", 1-800-922-4455. ALL UTILITY LOCATIONS THAT DO NOT MATCH THE VERTICAL OR HORIZONTAL CONTROL SHOWN ON THE PLANS SHALL IMMEDIATELY BE BROUGHT TO THE ATTENTION OF THE ENGINEER FOR RESOLUTION.
- 5. SLR INTERNATIONAL CORPORATION ACCEPTS NO RESPONSIBILITY FOR THE ACCURACY OF MAPS AND DATA WHICH HAVE BEEN SUPPLIED BY OTHERS.
- 6. INLAND WETLANDS AND WATERCOURSES ON SITE WERE DELINEATED IN THE FIELD ON APRIL 25 AND MAY 21, 2024 BY MATTHEW J. SANFORD, REGISTERED SOIL SCIENTIST FROM SLR CONSULTING.
- 7. A DEEP STORMWATER GENERAL PERMIT IS REQUIRED PRIOR TO INITIATION OF CONSTRUCTION.
- 8. ALL UTILITY SERVICES ARE TO BE UNDERGROUND. THE EXACT LOCATION AND SIZE OF ELECTRIC, TELEPHONE, CABLE TELEVISION, SANITARY SEWER AND PUBLIC WATER ARE TO BE DETERMINED BY THE RESPECTIVE UTILITY COMPANIES.
- 9. ALL STORM PIPING SHALL BE HIGH DENSITY POLYETHYLENE PIPE (HDPE) UNLESS OTHERWISE NOTED.
- 10. ALL PROPOSED CONTOURS AND SPOT ELEVATIONS INDICATE FINISHED GRADE.
- 11. ALL GRAVITY SANITARY SEWER PIPE SHALL BE SDR35 UNLESS OTHERWISE NOTED.
- 12. ALL FUEL, OIL, PAINT, OR OTHER HAZARDOUS MATERIALS USED ON SITE SHOULD BE STORED IN A SECONDARY CONTAINER AND REMOVED TO A LOCKED INDOOR AREA DURING NON-WORK HOURS.
- 13. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ANY UTILITIES INCLUDING IRRIGATION PIPES PRIOR TO THE START OF
- 14. ALL DIMENSIONS AND ELEVATIONS SHALL BE VERIFIED IN THE FIELD PRIOR TO CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER.
- 15. SEDIMENT AND EROSION CONTROL MEASURES AS DEPICTED ON THESE PLANS AND DESCRIBED WITHIN THE SEDIMENT AND EROSION CONTROL NARRATIVE SHALL BE IMPLEMENTED AND MAINTAINED UNTIL PERMANENT COVER AND STABILIZATION IS ESTABLISHED. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL CONFORM TO THE "CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL - 2023, AS AMENDED, AND IN ALL CASES BEST MANAGEMENT PRACTICES SHALL PREVAIL.
- 16. ALL DISTURBED AREAS SHALL RECEIVE A MINIMUM OF 6" TOPSOIL AND BE SEEDED WITH SPECIFIED SEED MIX, AS SHOWN ON THE PLANS.
- 17. IN ALL CASES, TOPSOIL AND OTHER CONSTRUCTION MATERIALS SHALL BE DRAWN FROM THE ON-SITE STOCKPILES OF EXISTING MATERIAL. ONLY WHEN ON-SITE STOCKPILES HAVE BEEN USED SHALL MATERIAL BE IMPORTED TO THE SITE.
- 18. ALL CONSTRUCTION MATERIALS AND METHODS SHALL CONFORM TO THE TOWN OF SALISBURY REOUIREMENTS AND TO THE APPLICABLE SECTIONS OF THE STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROADS, BRIDGES, FACILITIES AND INCIDENTAL CONSTRUCTION, FORM 818 AND ADDENDUMS.
- 19. THE PLANS REQUIRE A CONTRACTOR'S WORKING KNOWLEDGE OF LOCAL, MUNICIPAL, WATER AUTHORITY, AND STATE CODES FOR UTILITY SYSTEMS. ANY CONFLICTS BETWEEN MATERIALS AND LOCATIONS SHOWN, AND LOCAL REQUIREMENTS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO THE EXECUTION OF WORK. THE ENGINEER WILL NOT BE HELD LIABLE FOR COSTS INCURRED TO IMPLEMENT OR CORRECT WORK WHICH DOES NOT CONFORM TO LOCAL CODE.
- 20. COMPLIANCE WITH THE PERMIT CONDITIONS IS THE RESPONSIBILITY OF BOTH THE CONTRACTOR AND PERMITEE.
- 21. THESE PLANS HAVE BEEN PREPARED FOR REGULATORY APPROVAL ONLY. THEY ARE NOT INTENDED FOR USE DURING CONSTRUCTION.
- 22. THE PROPERTY OWNER MUST MAINTAIN (REPAIR/REPLACE WHEN NECESSARY) THE EROSION CONTROLS UNTIL ALL DEVELOPMENT ACTIVITY IS COMPLETED AND ALL DISTURBED AREAS ARE PERMANENTLY STABILIZED.




WAKE ROBIN INN

104 & 106 SHARON ROAD

JULY 18, 2024



PROJECT SITE VICINITY MAP:



PREPARED BY:






PREPARED FOR:

ARADEV LLC 352 ATLANTIC AVENUE, UNIT 2 BROOKLYN, NY 11217


LIST OF DRAWINGS


NO.	NAME	TITLE
01		TITLE SHEET
02	EX	EXISTING CONDITIONS
03	LA	SITE PLAN - LAYOUT
04	LS	SITE PLAN - LANDSCAPING
05	GR	SITE PLAN - GRADING
06	UT	SITE PLAN - UTILITIES
07	SE-1	SEDIMENT & EROSION CONTROL PLAN
08	SE-2	SEDIMENT & EROSION CONTROL NOTES & DETAILS
09-14	SD-1 - SD-6	SITE DETAILS




























SEDIMENT & EROSION CONTROL SPECIFICATIONS

GENERAL:

THESE GUIDELINES SHALL APPLY TO ALL WORK CONSISTING OF ANY AND ALL TEMPORARY AND/OR PERMANENT MEASURES TO CONTROL WATER POLLUTION AND SOIL EROSION, AS MAY BE REQUIRED, DURING THE CONSTRUCTION OF THE PROJECT.

NOT TO POLLUTE ANY WETLANDS, WATERCOURSE, WATER BODY, AND CONDUIT CARRYING TO A FENCE POST AND BURIED INTO THE GROUND, SHALL BE INSTALLED AND MAINTAINED WATER, ETC. THE CONTRACTOR SHALL LIMIT, INSOFAR AS POSSIBLE, THE SURFACE AREA AS REQUIRED TO CHECK EROSION AND REDUCE SEDIMENTATION. OF EARTH MATERIALS EXPOSED BY CONSTRUCTION METHODS AND IMMEDIATELY PROVIDE PERMANENT AND TEMPORARY POLLUTION CONTROL MEASURES TO PREVENT CONTAMINATION OF ADJACENT WETLANDS, WATERCOURSES, AND WATER BODIES, AND TO PREVENT, INSOFAR AS POSSIBLE, EROSION ON THE SITE.

LAND GRADING:

THE RESHAPING OF THE GROUND SURFACE BY EXCAVATION AND FILLING OR A COMBINATION OF BOTH, TO OBTAIN PLANNED GRADES, SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING CRITERIA:

- a. THE CUT FACE OF EARTH EXCAVATION SHALL NOT BE STEEPER THAN TWO HORIZONTAL SECTIONS OF FILTER FABRIC SHALL OVERLAP MINIMUM OF TWO FEET (2'). TO ONE VERTICAL (2:1).
- b. THE PERMANENT EXPOSED FACES OF FILLS SHALL NOT BE STEEPER THAN TWO HORIZONTAL TO ONE VERTICAL (2:1).
- c. THE CUT FACE OF ROCK EXCAVATION SHALL NOT BE STEEPER THAN ONE HORIZONTAL TO TWO VERTICAL (1:2).
- d. PROVISIONS SHOULD BE INCLUDED TO CONVEY SURFACE WATER SAFELY TO STORM DRAINS TO PREVENT SURFACE RUNOFF FROM DAMAGING CUT FACES AND FILL SLOPES.
- e. NO FILL SHOULD BE PLACED WHERE IT WILL SLIDE OR WASH UPON THE INTO ADJACENT WETLANDS, WATERCOURSES, OR WATER BODIES.
- PRIOR TO ANY RE-GRADING, A STABILIZED CONSTRUCTION ENTRANCE SHALL BE PLACED AT THE ENTRANCE TO THE WORK AREA IN ORDER TO REDUCE MUD AND OTHER

TOPSOILING:

SEDIMENTS FROM LEAVING THE SITE.

TOPSOIL SHALL BE SPREAD OVER ALL EXPOSED AREAS IN ORDER TO PROVIDE A SOIL MEDIUM HAVING FAVORABLE CHARACTERISTICS FOR THE ESTABLISHMENT, GROWTH, AND MAINTENANCE OF VEGETATION.

UPON ATTAINING FINAL SUBGRADES, SCARIFY SURFACE TO PROVIDE A GOOD BOND WITH TOPSOIL.

REMOVE ALL LARGE STONES, TREE LIMBS, ROOTS AND CONSTRUCTION DEBRIS.

APPLY LIME ACCORDING TO SOIL TEST OR AT THE RATE OF TWO (2) TONS PER ACRE.

MATERIAL

- . TOPSOIL SHOULD HAVE PHYSICAL, CHEMICAL, AND BIOLOGICAL CHARACTERISTICS FAVORABLE TO THE GROWTH OF PLANTS.
- 2. TOPSOIL SHOULD HAVE A SANDY OR LOAMY TEXTURE.
- 3. TOPSOIL SHOULD BE RELATIVELY FREE OF SUBSOIL MATERIAL AND MUST BE FREE O STONES (OVER 1" IN DIAMETER), LUMPS OF SOIL, ROOTS, TREE LIMBS, TRASH, OR CONSTRUCTION DEBRIS. IT SHOULD BE FREE OF ROOTS OR RHIZOMES SUCH AS THISTLE, NUTGRASS, AND QUACKGRASS.
- 4. AN ORGANIC MATTER CONTENT OF SIX PERCENT (6%) IS REQUIRED. AVOID LIGHT COLORED SUBSOIL MATERIAL.
- 5. SOLUBLE SALT CONTENT OF OVER 500 PARTS PER MILLION (PPM) IS LESS SUITABLE. AVOID TIDAL MARSH SOILS BECAUSE OF HIGH SALT CONTENT AND SULFUR ACIDITY.
- 6. THE pH SHOULD BE MORE THAN 6.0. IF LESS, ADD LIME TO INCREASE pH TO AN ACCEPTABLE LEVEL

APPLICATION:

- AVOID SPREADING WHEN TOPSOIL IS WET OR FROZEN.
- SPREAD TOPSOIL UNIFORMLY TO A DEPTH OF AT LEAST SIX INCHES (6"), OR TO THE DEPTH SHOWN ON THE PLANS.

TEMPORARY VEGETATIVE COVER:

FEMPORARY VEGETATIVE COVER SHALL BE ESTABLISHED ON ALL UNPROTECTED AREAS THAT PRODUCE SEDIMENT, AREAS WHERE FINAL GRADING HAS BEEN COMPLETED, AND AREAS WHERE THE ESTIMATED PERIOD OF BARE SOIL EXPOSURE IS LESS THAN 12 MONTHS. TEMPORARY VEGETATIVE COVER SHALL BE APPLIED IF AREAS WILL NOT BE PERMANENTLY SEEDED BY SEPTEMBER 1.

SITE PREPARATION:

- 1. INSTALL REOUIRED SURFACE WATER CONTROL MEASURES.
- 2. REMOVE LOOSE ROCK, STONE, AND CONSTRUCTION DEBRIS FROM AREA.
- . APPLY LIME ACCORDING TO SOIL TEST OR AT A RATE OF ONE (1) TON OF GROUND DOLOMITIC LIMESTONE PER ACRE (5 LBS. PER 100 SQ. FT.).
- 4. APPLY FERTILIZER ACCORDING TO SOIL TEST OR AT THE RATE OF 300 LBS. OF 10-10-10 SUITABLE EQUIPMENT (EXCEPT WHEN HYDROSEEDING). PER ACRE (7 LBS. PER 1,000 SQ. FT.) AND SECOND APPLICATION OF 200 LBS. OF 10-10-10- (5 LBS. PER 1,000 SQ. FT.) WHEN GRASS IS FOUR INCHES (4") TO SIX
- INCHES (6") HIGH. APPLY ONLY WHEN GRASS IS DRY. . UNLESS HYDROSEEDED, WORK IN LIME AND FERTILIZER TO A DEPTH OF FOUR (4") INCHES USING A DISK OR ANY SUITABLE EOUIPMENT.
- 6. TILLAGE SHOULD ACHIEVE A REASONABLY UNIFORM LOOSE SEEDBED. WORK ON CONTOUR IF SITE IS SLOPING.

ESTABLISHMENT:

- APPLY SEED UNIFORMLY ACCORDING TO THE RATE INDICATED BY BROADCASTING, DRILLING, OR HYDRAULIC APPLICATION.
- 2. UNLESS HYDROSEEDED, COVER RYEGRASS SEEDS WITH NOT MORE THAN 1/4 INCH OF SOIL USING SUITABLE EQUIPMENT.
- 3. MULCH IMMEDIATELY AFTER SEEDING IF REQUIRED. (REFER TO TEMPORARY OR PERMANENT VEGETATIVE COVER REQUIREMENTS.) APPLY STRAW MULCH AND ANCHOR TO SLOPES GREATER THAN 3% OR WHERE CONCENTRATED FLOW WILL OCCUR.

PERMANENT VEGETATIVE COVER:

PERMANENT VEGETATIVE COVER SHALL BE ESTABLISHED AS VARIOUS SECTIONS OF THE PROJECT ARE COMPLETED IN ORDER TO STABILIZE THE SOIL, REDUCE DOWNSTREAM DAMAGE FROM SEDIMENT AND RUNOFF, AND TO ENHANCE THE AESTHETIC NATURE OF THE SITE. IT WILL BE APPLIED TO ALL CONSTRUCTION AREAS SUBJECT TO EROSION WHERE FINAL GRADING HAS BEEN COMPLETED AND A PERMANENT COVER IS NEEDED.

SITE PREPARATION:

- 1. INSTALL REQUIRED SURFACE WATER CONTROL MEASURES.
- 2. REMOVE LOOSE ROCK, STONE, AND CONSTRUCTION DEBRIS FROM AREA.
- 3. PERFORM ALL PLANTING OPERATIONS PARALLEL TO THE CONTOURS OF THE SLOPE.
- 4. APPLY TOPSOIL AS INDICATED ELSEWHERE HEREIN.
- 5. APPLY FERTILIZER ACCORDING TO SOIL TEST OR:
- SPRING SEEDING: WORK DEEPLY IN SOIL, BEFORE SEEDING, 300 LBS. OF 10-10-10 FERTILIZER PER ACRE (7 LBS. PER 1,000 SQ. FT.); THEN SIX (6) TO EIGHT (8) WEEKS LATER, APPLY ON THE SURFACE AN ADDITIONAL 300LBS. OF 10-10-10 FERTILIZER PER ACRE. AFTER SEPTEMBER 1, TEMPORARY VEGETATIVE COVER SHALL BE APPLIED.
- FALL SEEDING: WORK DEEPLY IN SOIL, BEFORE SEEDING, 600 LBS. OF 10-10-10 FERTILIZER PER ACRE (14 LBS. PER 1,000 SQ. FT.).

EROSION CHECKS:

GENERAL

FEMPORARY PERVIOUS BARRIERS USING BALES OF STRAW, HELD IN PLACE WITH STAKES IN GENERAL, ALL CONSTRUCTION ACTIVITIES SHALL PROCEED IN SUCH A MANNER SO AS DRIVEN THROUGH THE BALES AND INTO THE GROUND OR GEOTEXTILE FABRIC FASTENED

CONSTRUCTION

BALES SHOULD BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT BALES. EACH BALE SHALL BE EMBEDDED INTO THE SOIL A MINIMUM OF FOUR (4") INCHES.

BALES SHALL BE SECURELY ANCHORED IN PLACE BY WOOD STAKES OR REINFORCEMENT BARS DRIVEN THROUGH THE BALES AND INTO THE GROUND. THE FIRST STAKE IN EACH

BALE SHALL BE ANGLED TOWARD THE PREVIOUSLY LAID BALE TO FORCE BALES TOGETHER.

GEOTEXTILE FABRIC SHALL BE SECURELY ANCHORED AT THE TOP OF A THREE FOOT (3') HIGH FENCE AND BURIED A MINIMUM OF FOUR INCHES (4") TO THE SOIL. SEAMS BETWEEN

INSTALLATION AND MAINTENANCE:

- 1. BALED STRAW EROSION BARRIERS SHALL BE INSTALLED AT ALL STORM SEWER INLETS. BALED STRAW EROSION BARRIERS AND GEOTEXTILE FENCE SHALL BE INSTALLED AT THE LOCATION INDICATED ON THE PLAN AND IN ADDITIONAL AREAS AS MAY BE DEEMED APPROPRIATE DURING CONSTRUCTION.
- ALL EROSION CHECKS SHALL BE MAINTAINED UNTIL ADJACENT AREAS ARE STABILIZED. 4. INSPECTION SHALL BE FREQUENT (AT MINIMUM BI-MONTHLY AND AFTER RAINFALL
- EVENTS GREATER THAN ONE HALF INCH) AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED.
- EROSION CHECKS SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFULNESS SO AS NOT TO BLOCK OR IMPEDE STORM WATER FLOW OR DRAINAGE.

TEMPORARY STABILIZATION FOR WINTER CONDITIONS:

ANY SIGNIFICANT AREAS OF EXPOSED SOIL WHICH HAVE BEEN DISTURBED AFTER OCTOBER 15TH SHALL BE TEMPORARILY STABILIZED BY ONE OF THE FOLLOWING METHODS UNTIL SUCH TIME THAT PERMANENT STABILIZATION MEASURES AND SEEDING CAN BE APPLIED, TYPICALLY AFTER MAY 15TH.

- 1. INSTALLATION OF AN ANCHORED EROSION CONTROL BLANKET. EROSION CONTROL BLANKETS SHOULD NOT BE INSTALLED ON SNOW OF GREATER THAN ONE INCH IN DEPTH OR ON FROZEN GROUND.
- 2. APPLICATION OF STRAW MULCH AT A RATE OF FOUR (4) TONS PER ACRE.
- 3. APPLICATION OF WOOD CHIP MULCH AT A MINIMUM DEPTH OF THREE INCHES (3"). WOOD CHIP MULCH SHOULD NOT BE USED ON SLOPES GREATER THAN 2:1 (H:V). ALL WOOD CHIP MULCH SHALL BE REMOVED PRIOR TO RESUMING SITE GRADING.

VEGETATIVE COVER SELECTION & MULCHING:

TEMPORARY VEGETATIVE COVER:

PERENNIAL RYEGRASS 3 LBS./1,000 SO.FT. (IOLUIUM PERENNE)

PERMANENT VEGETATIVE COVER


- TURFGRASS MIX OR EQUAL: RECOMMENDED APPLICATION RATE: 1 POUND PER 1,750 SF SEED MIX SPECIES: CREEPING RED FESCUE (Festuca rubra var. rubra (endophyte enchanced)) - 15%, PERENNIAL RYEGRASS (Lolium multiflorum) - 15%, KENTUCKY BLUEGRASS (Poa pratensis "KenBlue') - 35%, CHEWINGS FESCUE (Festuca rubra var. commutate 'Tiffany') - 15%.
- FEMPORARY MULCHING: STRAW AT 70-90 LBS./1,000 SQ.FT. (TEMPORARY VEGETATIVE AREAS) WOOD FIBER IN HYDROMULCH SLURRY 25-50 LBS./1,000 SQ. FT.
- 2. WITHIN 100-FOOT REGULATED UPLAND AREAS FROM WETLANDS: RECOMMENDED APPLICATION RATE: 1 POUND PER 1,250 SF SEED MIX SPECIES: NEW ENGLAND EROSION CONTROL/RESTORATION MIX (FOR MOIST SITES) OR 1 POUND PER 1,750 SF NEW ENGLAND CONSERVATION/WILDLIFE MIX

ESTABLISHMENT:

- . SMOOTH AND FIRM SEEDBED WITH CULTIPACKER OR OTHER SIMILAR EQUIPMENT PRIOR TO SEEDING (EXCEPT WHEN HYDROSEEDING).
- 2. SELECT ADAPTED SEED MIXTURE FOR THE SPECIFIC SITUATION. NOTE RATES AND THE SEEDING DATES (REFER TO TEMPORARY OR PERMANENT VEGETATIVE COVER REOUIREMENTS).
- 3. APPLY SEED UNIFORMLY ACCORDING TO RATE INDICATED, BY BROADCASTING, DRILLING, OR HYDRAULIC APPLICATION.
- 4. COVER GRASS AND LEGUME SEED WITH NOT MORE THAN 1/4 INCH OF SOIL WITH
- 5. MULCH IMMEDIATELY AFTER SEEDING, IF REOUIRED, ACCORDING TO TEMPORARY MULCHING SPECIFICATIONS. (REFER TO TEMPORARY OR PERMANENT VEGETATIVE COVER REOUIREMENTS).
- 6. USE PROPER INOCULANT ON ALL LEGUME SEEDINGS, USE FOUR (4) TIMES NORMAL RATES WHEN HYDROSEEDING.
- 7. THE USE OF SOD IS AN ACCEPTABLE ALTERNATIVE WHERE THERE IS A HEAVY CONCENTRATION OF WATER AND IN CRITICAL AREAS WHERE IT IS IMPORTANT TO GET A OUICK VEGETATIVE COVER TO PREVENT EROSION.

MAINTENANCE:


- TEST FOR SOIL ACIDITY EVERY THREE (3) YEARS AND LIME AS REQUIRED. 2. ON SITES WHERE GRASSES PREDOMINATE, BROADCAST ANNUALLY 500 POUNDS OF 10-10-10 FERTILIZER PER ACRE (12 LBS. PER 1,000 SQ. FT.) OR AS NEEDED ACCORDING TO ANNUAL SOIL TESTS.
- 3. ON SITES WHERE LEGUMES PREDOMINATE, BROADCAST EVERY THREE (3)YEARS OR AS INDICATED BY SOIL TEST 300 POUNDS OF 0-20-20 OR EQUIVALENT PER ACRE (8 LBS PER 1,000 SQ. FT.).



<u>NOTE:</u> STABILIZED CONSTRUCTION ENTRANCE SHALL BE INSTALLED AND MAINTAINED DURING OPERATIONS WHICH PROMOTE VEHICULAR TRACKING OF MUD

CONSTRUCTION ENTRANCE PAD (CE)

NOT TO SCALE



STRAW WATTLE	(SW)
NOT TO SCALE	

EROSION CONTROL MEASURE	CONTROL OBJECTIVE	INSPECTION/MAINTENANCE
TEMPORARY SEDIMENT TRAP (TST)	- DETAIN SEDIMENT-LADEN RUNOFF FROM SMALL DISTURBED AREAS LONG ENOUGH TO ALLOW A MAJORITY OF THE SEDIMENT TO SETTLE OUT.	INSPECT AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH A RAINFALL OF 0.5 INCHES OR MORE. STONE OUTLET SHOULD BE AT LEAST 0.5 FEET BELOW CREST OF EMBANKMENT. SEDIMENT MUST BE REMOVED WHEN ACCUMULATION REACHES ½ OF THE REQUIRED WET STORAGE.
SILT FENCE (SF) (RELATED: IP, STK)	 - INTERCEPT, AND REDIRECT/DETAIN SMALL AMOUNTS OF SEDIMENT FROM SMALL DISTURBED AREAS. - DECREASE VELOCITY OF SHEET FLOW. - PROTECT SENSITIVE SLOPES OR SOILS FROM EXCESSIVE WATER FLOW. 	INSPECT AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH A RAINFALL OF 0.5 INCHES OR MORE. ACCUMULATED SEDIMENT MUST BE REMOVED ONCE ITS DEPTH IS EQUAL TO ½ THE TRENCH HEIGHT. INSPECT FREQUENTLY DURING PUMPING OPERATIONS IF USED FOR DEWATERING OPERATIONS.
STRAW WATTLE (SW)	 - INTERCEPT, AND REDIRECT/DETAIN SMALL AMOUNTS OF SEDIMENT FROM SMALL DISTURBED AREAS. - DECREASE VELOCITY OF SHEET FLOW. - PROTECT SENSITIVE SLOPES OR SOILS FROM EXCESSIVE WATER FLOW. 	INSPECT AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH A RAINFALL OF 0.5 INCHES OR MORE. ACCUMULATED SEDIMENT MUST BE REMOVED ONCE THE DEPTH OF SEDIMENT IS WITHIN 3" OF THE TOP OF THE BARRIER. INSPECT FREQUENTLY DURING PUMPING OPERATIONS IF USED FOR DEWATERING OPERATIONS.
TEMPORARY DIVERSION BERM/SWALE (TBS) OR TEMPORARY SWALE (TBS)	- MINIMIZE VELOCITY AND CONCENTRATION OF SHEET FLOW ACROSS CONSTRUCTION SITE TO A SEDIMENT TRAPPING FACILITY. - DIVERT WATER ORIGINATING FROM UNDISTURBED AREA AWAY FROM CONSTRUCTION.	WHEN LOCATED WITHIN CLOSE PROXIMITY TO ONGOING CONSTRUCTION ACTIVITIES, INSPECT AT THE END OF EACH WORK DAY AND IMMEDIATELY REPAIR DAMAGES. OTHERWISE INSPECT AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH A RAINFALL OF 0.5 INCHES OR MORE. REPAIR THE TEMPORARY MEASURE AND ANY OTHER ASSOCIATED MEASURES WITHIN 24 HOURS.
CONSTRUCTION ENTRANCE (CE)	- REDUCE THE TRACKING OF SEDIMENT OFF-SITE ONTO PAVED SURFACES.	INSPECT AT THE END OF EACH WORK DAY AND IMMEDIATELY REPAIR DAMAGES. PERIODIC ADDITION OF STONE, OR LENGTHENING OF ENTRANCE MAY BE REQUIRED AS CONDITIONS DEMAND. ALL SEDIMENT SPILLED, DROPPED, WASHED, OR TRACKED ONTO PAVED SURFACES AS A RESULT OF INEFFICIENCY OF CONSTRUCTION ENTRANCE SHALL BE IMMEDIATELY REMOVED.
CATCH BASIN INLET PROTECTION (IP)	- PROHIBIT SILT IN CONSTRUCTION-RELATED RUNOFF FROM ENTERING STORM DRAINAGE SYSTEM.	INSPECT AFTER ANY RAIN EVENT. IF FILTER BAG INSIDE CATCH BASIN CONTAINS MORE THAN 6" OF SEDIMENT, REMOVE SEDIMENT FROM BAG. CHECK SURROUNDING SILT FENCE AND HAY BALES PER NOTED ABOVE.
STOCKPILE PROTECTION (STK)	- RETAIN SOIL STOCKPILE IN LOCATIONS SPECIFIED, AND REDUCE WATER-TRANSPORT.	INSPECT SILT FENCE AT THE END OF EACH WORK DAY AND IMMEDIATELY REPAIR DAMAGES. PERIODIC REINFORCEMENT OF SILT FENCE, OR ADDITION OF HAY BALES MAY BE NECESSARY.
DUST CONTROL	- TO PREVENT MOVEMENT OF DUST FROM EXPOSED SOIL SURFACES, WHICH MAY CAUSE BOTH OFF-SITE AND ON-SITE DAMAGE, BE A HEALTH HAZARD TO HUMANS, WILDLIFE, AND PLANT LIFE, OR CREATE A HAZARD BY REDUCING TRAFFIC VISIBILITY.	-USE MECHANICAL SWEEPING DAILY ON PAVED AREAS WHERE DUST AND FINE MATERIALS ACCUMULATE, IF HEAVILY TRAFFICKED AND SEDIMENT ACCUMULATES QUICKLY. MOISTEN UNPAVED TRAVELWAYS TO CONTROL DUST WHEN EVIDENCE OF AIRBORNE DUST.



HAY BALES MAY BE DUE TO RAIN EVENTS THE STOCKPILE IS USED OR REMOVED. - FAILURE OF SILT FENCE -REPEAT APPLICATION OF DUST CONTROL E DUST AND FINE MATERIALS

-AIRBORNE DUST


08 OF 14 SE-2


MEASURES UNTIL ALL AREAS ARE PERMANENTLY


STABILIZED, VEGETATED, AND PAVED, OR AS

LONG AS THERE IS AIRBORNE DUST.


22100.00001















SD-10


AQUARION

Stewards of the Environment


Water Company


NOT TO SCALE






SD-3










5. STANDARD	PERCEN	TAG	E PASSING
SIEVE	SIZE	ΒY	WEIGHT

VE SIZE	BY WEIG
NCH	100
). 4	60-95
0.10	50-95
. 40	30-75
0.100	20-65
. 200	10-40

WAKE ROBIN INN REDEVELOPMENT All ш - S SM SM TR **AS NOTED** JULY 18, 2024 22100.00001 13 OF 14 SD-5



OUTLET PROTECTION ID	TYPE	SP (FT)	RP (FT)	LA (FT)	W1 (FT)	W2 (FT)	D (IN)
FES 12	MODIFIED TYPE B	1.0	1.0	12.0	3.0	8.0	12
FES 23	MODIFIED TYPE B	0.67	0.67	10.0	2.0	6.0	12